



BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprise)
O/o THE EXECUTIVE ENGINEER
BSNL CIVIL DIVISION, East Hill, CALICUT - 673 005

No. 20 (39) / EE/CLT/BSNL/2015/647

Dated: 20th July 2015

NOTICE INVITING QUOTATIONS

For and on behalf of the BSNL, sealed competitive Quotations are invited from eligible Agencies for the following work. The quotations, strictly in the attached Schedule of quantities (Page 2), should reach this office in sealed covers before 3 P.M. on **27th July 2015**. Quotations will be opened at 15.30 hrs on the same day by the undersigned in the presence of the participating bidders who are present at the time of opening.

Name of work: **Conducting Soil Investigation for Proposed W&C Block at District Hospital, Nilambur.**

Schedule of quantities separately attached at Page no 2

CONDITIONS:

- 1 Quotations, strictly in the given format, shall be submitted in sealed covers, addressed to the undersigned, before 3.00 PM on **27th July 2015**.
- 2 The period allowed for completion of the work is 30 days from the date of issue of Work Order.
3. The Work shall be carried out as per standard specifications and as per the directions of the Engineer-in-Charge.
4. The rates shall include cost of all labour, materials, VAT & other service charges and nothing extra will be paid on any account. **The extent of service tax payable by the service provider shall be paid by the agency and is not reimbursable.**

(Signature, Name & Address of Agency)

EXECUTIVE ENGINEER
BSNL, CIVIL DIVISION
CALICUT- 673005

SCHEDULE OF QUANTITIES

Name of work :- Conducting Soil Investigation for Proposed W&C Block at District Hospital, Nilambur.

Adns :	
Corn :	
Omsn:	
Owrt :	
EE (C)	

SI No	Description of item	Qty	Rate (in fig & words)	Unit	Amount
1	Mobilization of drilling machinery and installation at site	1.00	Job	One Job	
2	Boring through all types of soils except rock upto a depth of 10M or upto a strata where N value greater than or equal to 100, whichever reaches earlier including collection of samples, conducting necessary in situ, tests etc. complete as directed.	3.00	bores	Each bore	
3	Boring through all types of soils except rock for additional depth beyond 10M and upto a strata where N value greater than or equal to 100 etc complete as directed.	30.00	Metres	One Mtr	
4	Drilling in rock i.e. strata in which N value>100	1.00	Metre	One Mtr	
5	Conducting necessary Laboratory tests on samples, compilation of test results and submission of report (five copies) for 2 bore holes along with recommendation for foundation design/data and assessment of SBC	1.00	Job	One Job	
TOTAL					

CONTRACTOR

EXECUTIVE ENGINEER(C)
BSNL CIVIL DIVISION, CALICUT